MYSORE RAILWAYS.

MYSORE DIVISION (OPEN LINES).

Notification, dated 20th July 1934.

Notice is hereby given that sealed tenders will be received at the Office of the Senior Executive Engineer, Mysore Railways, Mysore, up-to 4 P.M., on the 13th August 1934 for the following works in connection with the Expansion of Mysore Railway Central Workshops, at Mysore. Separate tenders should be sent for each of the works which will be disposed of separately on their merits.

1. Constructing a new Wagon shop.
2. Constructing Works Superintendent's Office.
3. Extending the existing Time Office.
4. Earth work for laying new tracks.

2. Every tender must be accompanied by an earnest money as noted against each work which should be paid to the Auditor, Mysore Railways, Mysore, duly intimating the Auditor the work for which the earnest money is paid, and the receipt thereof enclosed along with the tender.

3. Tenders should be submitted in special forms which can be obtained from the Senior Executive Engineer, Mysore Railways, Mysore, on payment of one Rupee for each form which is not refundable, under any circumstances.

4. No tender will be considered which is not sent in the prescribed form.

5. Tenders which give rates saying as per estimate rates or so much per cent above or below estimate rates will not be considered. The rates should be noted both in figures and in words. Corrections, if any, should be initialled by the contractor himself.

6. The work should be started within two weeks from date of orders to start the work and completed within the period noted for each work with a guaranteed monthly rate of progress. The accompanying Schedules give the approximate quantities of works, and these quantities are not guaranteed.

7. The time limit specified should be strictly adhered to and any violation of this will render the contractor liable to forfeit his five per cent deposit amount not as a penalty, but as ascertained and liquidated damages recoverable accordingly.

8. The names of the accepted tenderers will be posted on the Notice Board of the Senior Executive Engineer's Office as soon as it is accepted. No enquiries regarding the acceptance or rejection of a tender will be replied.

9. The earnest money of the unsuccessful tenderers will be returned as soon as possible after the tenders are disposed of while those of the successful tenderers, will be accepted as part payment towards the security deposit due as per para 11.

10. The final acceptance of the tenders will rest with the Agent for items Nos. 1 and 2 and with the Superintendent, Way and Works, for items 3 and 4 who do not bind themselves to accept the lowest or any tender and who further reserve to themselves the right to reject without assigning any reasons therefor any or all the tenders or any portion of any one tender.

11. The successful tenderers should deposit with the Auditor, Mysore Railways, Mysore, before he signs the Schedule Agreement five per cent of the value of the work for which the tender is accepted as security for due fulfilment of the terms of the Agreement.

12. The successful tenderers should execute within eight days from the date of notification of acceptance of tenders, the Schedule Agreement. Failure to comply with this condition will render the contract null and void and the earnest money forfeited.

13. Plans, specifications and designs and other details of work to be executed are available for inspection in the Senior Executive Engineer's Office, Mysore Railways, Mysore, where intending tenderers may obtain required information during office hours.

14. In all matters of dispute regarding rates, measurements, quality of work, etc., and in all disputes of any kind the decision of the Superintendent, Way and Works, Mysore Railways, will be final and legally binding.

15. Contractors should make their own arrangements for water required for the works.

16. Specification for works will be according to Marryat's Hand Book, Vol. I.

Constructing Wagon Shop.

SCHEDULE.

Serial No.	Particulars	Per	Quantity
1	Earth work, lowering the ground in all soils to formation level including hard rock, if any, carting the spoil to places shown by the Department up to a maximum lead of 2,000 feet and spreading the spoil evenly as per levels fixed by the Department	1,000 C.ft.	3,00,000 C.ft.
2	Earth work, excavating for foundations in all soils including hard rock except blasting, carting the spoil to places shown by the Department up to a maximum lead of 2,000 feet and spreading it evenly as per levels fixed by the Department	1,000 ,,	10,000 ,,
3	Earth work excavating for foundations in hard rock to be removed by blasting, carting the spoil to places shown by the Department up to a maximum lead of 200 feet and stacking	1,000 ,,	1,000 ,,
4	Concrete, broken stone in sand mortar	100 ,,	4,600 ,,
5	Concrete, broken stone in cement mortar (1 cement, $2\frac{1}{2}$ sand and 5 Stone jelly small enough to pass through a $\frac{3}{4}$" ring) including necessary frame work for laying concrete	100 ,,	1,440 ,,
6	Coursed rubble masonry in sand mortar, first class, including bond stones, dressing corner stones of walls, pilasters, jambs of doors, windows, etc.	100 ,,	23,000 ,,
7	Coursed rubble masonry in cement mortar, first class, including bond stones, dressing corner stones of pilasters, etc.	100 ,,	2,300 ,,
8	Chunam pointing	100 S.ft.	29,000 S.ft.
9	Ferro concrete honey-comb work as per approved design ..	S.ft.	300 ,,
10	Cement concrete bond, bearing, lintel slabs including lead lift and necessary moulds (proportion of concrete 1 cement, 3 sand and 6 stone jelly small enough to pass through $\frac{3}{4}$ inch ring)	100 C.ft.	1,500 C.ft.
11	Cement concrete cornice and coping slabs including lead, lift and necessary moulds (proportion of concrete 1 cement, 3 sand and 6 stone jelly small enough to pass through a $\frac{3}{4}$ inch ring)	100 ,,	2,100 ,,
12	Teakwood partition with 20 B.W.G. Glavanised Iron Plain sheet panels as per approved design	S.ft.	450 S.ft.
13	Flooring with 4" thick burnt stone slabs two line dressed over 6" thick concrete (broken stone in sand mortar) bed including cement pointing	100 S.ft.	3,500 S.ft.
14	Silicate painting, two coats	100 ,,	29,000 ,,
15	Unloading iron and steel materials from wagons and stacking including a lead of 300 feet	Ton	140 Tons

N.B.—The earnest money is Rs. 500 and the work should be completed within eight months from the date of orders to start the work.

Constructing Works, Superintendent's Office.

SCHEDULE.

Serial No.	Particulars	Per	Quantity
1	Earth work, excavating for foundations in all soils carting the spoil to places shown by the Department up to a maximum lead of 500 feet and spreading the spoil evenly as per levels fixed by the Department	1,000 C.ft.	3,600 C.ft.
2	Concrete, broken stone in sand mortar	100 ,,	1,500 ,,

Serial No.	Particulars	Per	Quantity
3	Coursed rubble masonry first class in sand mortar, including bond stones and dressing corner stones of walls	100 C.ft.	2,500 C.ft.
4	Burnt brick in sand mortar	100 ,,	1,080 ,,
5	Burnt brick in prepared mud	100 ,,	3,800 ,,
6	Arch work, burnt brick in sand mortar including centering charges	100 ,,	100 ,,
7	Burnt stone slabs 6″ thick dressed and fixed in sand mortar	S.ft.	646 S.ft.
8	Do two lines dressed	,,	224 ,,
9	Conveying, hoisting and fixing in position R. S. Beams including drilling holes for holding down bolts, etc.	Cwt.	14 Cwts.
10	Teakwood trusses 20 ft. clear span as per design of the existing Time Office including two coats of wood oiling	Each	4
11	Teakwood wrought and put up including two coats of wood oiling	C.ft.	200 C.ft.
12	Roofing with Pucca Terrace	100 S.ft.	1,400 S.ft.
13	Roofing with first class Mangalore pattern Yelahanka tiles over 2″×1″ Teak reepers including chunam borders, etc., complete	100 S.ft.	1,500 ,,
14	Mangalore pattern Yelahanka ridge tiles set in mortar	R.ft.	60 R.ft.
15	Teakwood ornamental eaves board 9″×1″ including two coats of Silicate painting	R.ft.	160 ,,
16	Masonry cornice 9″×9″	,,	210 ,,
17	Masonry cornice 6″×6″	,,	80 ,,
18	Teakwood panelled doors with hinges, hasps, brass handles, tower bolts, etc., complete	S.ft.	350 S.ft.
19	Teakwood windows with panelled shutters out side and ¾″ iron bars and glazed shutters inside with hinges, tower bolts, handles, etc., complete	,,	263 ,,
20	Teakwood glazed ventilators	,,	160 ,,
21	Do circular	,,	7 ,,
22	Chunam plastering	100 S.ft.	10,000 S.ft.
23	Chunam pointing	100 ,,	700 ,,
24	White and colour washing	100 ,,	11,000 ,,
25	Flooring with 1½″ thick Cuddapah slabs over 4″ thick concrete (broken stone in sand mortar) bed including cement pointing, etc., complete	100 ,,	2,000 ,,
26	Silicate painting, two coats	100 ,,	2,000 ,,
27	Cast Iron 4″ diameter pipes including bends, shoes, etc., complete	R.ft.	80 R.ft.
28	Teakwood sun shades including two coats of silicate painting	Each	15
29	Brick in mortar masonry plain parapet wall, two feet high	R.ft.	200 R.ft.
30	Teakwood finials	Each	2
31	Teakwood pendents	,,	4

Notes.—1. The earnest money is Rs. 300 and the work should be completed within six months from date of orders to start the work.

2. Railway Material Certificate will be issued for tiles and Cuddapah slabs.

3. The designs of Teakwood doors, windows, ventilators, cornice, parapet walls, eaves boards and sun shades may be seen at the Senior Executive Engineer's Office, Mysore.

4. Measurements of doors, windows, ventilators will be given for the clear inside dimensions.

Extending the Time Office.

SCHEDULE.

Serial No.	Particulars	Per	Quantity
1	Earth work excavating for foundation in all soils, carting the spoil to places shown by the Department up to a maximum lead of 500 feet and spreading the spoil evenly as per levels fixed by the Department	1,000 C.ft.	1,500 C.ft.
2	Concrete broken stone in sand mortar	100 ,,	900 ,,
3	Dismantling brick masonry and carting the spoil to places shown by the Department up to maximum lead of 500 feet and spreading the spoil evenly as per levels fixed by the Department	100 ,,	600 ,,
4	Brick in sand mortar with released bricks	100 ,,	200 ,,
5	Do new bricks	100 ,,	1,700 ,,
6	Brick in prepared mud with new bricks	100 ,,	2,000 ,,
7	Burnt stone slabs 6″ thick dressed and fixed in sand mortar	S.ft.	350 S.ft.
8	Removing, hoisting and fixing in new position burnt stone slabs in sand mortar	,,	150 ,,
9	Burnt stone slabs 6″ thick, two line dressed and fixed in sand mortar	,,	330 ,,
10	Drilling holes in 6″ thick burnt stone slabs	Each	32
11	Teakwood Trusses for 20 feet clear span as per existing design	,,	4
12	Teakwood wrought and put up including two coats of wood oiling	C.ft.	120 C.ft.
13	Roofing with first class Mangalore pattern Yelahanka tiles over 2″×1″ teak reepers including chunam borders, etc., complete	100 S.ft.	2,300 S.ft.
14	Mangalore pattern Yelahanka ridge tiles set in mortar ..	R.ft.	80 R.ft.
15	Removing Mangalore tiled roofing, rafters and refixing them	100 S.ft.	220 S.ft.
16	Chunam plastering	100 ,,	4,600 ,,
17	Masonry cornice 6″×6″	R.ft.	60 R.ft.
18	Mortar panels	S.ft.	60 S.ft.
19	White and colour washing	100 S.ft.	4,600 S.ft.
20	Teakwood, panelled doors with hinges, hasps, brass handles, etc., complete	S.ft.	252 ,,
21	Teakwood windows with glazed shutters inside and ¾″ iron bars, panelled shutters outside with hings, tower bolts, handles, etc., complete	,,	48 ,,
22	Teakwood glazed ventilators	,,	9 ,,
23	Removing, hositing and fixing in position Teakwood glazed ventilators	Each	1
24	Flooring with 1½″ thick Cuddapah slabs over 4″ thick concrete (broken stone in sand mortar) bed including cement point, etc., complete	100 S.ft.	1,400 S.ft.
25	Teakwood ornamental eaves board including two coats of silicate painting	R.ft.	210 R.ft.
26	Teakwood railing with 1½′×1″ teak wood planks over it, etc., complete including two coats of wood oiling ..	,,	200 ,,
27	Dismantling and rebuilding masonry pillars	Each	2
28	Assembling and conveying and fixing in position ornamental railings, gates, etc.	Cwt.	60 Cwts.
29	Removing, conveying and re-fixing ornamental railings, gates, etc.	,,	20 ,,
30	Silicate painting, two coats	100 S.ft.	1,000 S.ft.

N.B.—1. The earnest money is Rs. 200 and the work should be completed within six months from date of orders to start the work.

2. Railway Materials Concession Certificates will be issued for Tiles and Cuddapah slabs.

3. The designs for doors, windows, ventilators, cornice, eaves boards, mortar panels, Teakwood railings can be seen at the Senior Executive Engineer's Office, Mysore Railways, Mysore.

4. Measurements of doors, windows, ventilators will be given for the clear inside dimentions.

Earth work for Laying Track.

SCHEDULE.

Serial No.	Particulars	Per	Quantity
1	Earth work cutting in all soils (including hard rock if any) in the Central Workshops area to the South of the proposed Wagon Shop and to the East of the existing tracks, carting the spoil to places shown by the Department up to a maximum lead of 2,000 feet and spreading the spoil evenly as per levels fixed by the Department	1,000 C.ft.	200,000 C.ft.

Note.—1. Excavation of side and check drains are included in the above quantity.

2. Measurements will be given as per ground sections recorded. The earnest money is Rs. 200 and the work should be completed within six months from date of orders to start the work.

R. N. MIRZA,
Senior Executive Engineer.

OFFICE OF THE DEPUTY DIRECTOR OF AGRICULTURE, SHIMOGA.

Notification No. B. 12-14—34-35, *dated 14th July* 1934.

Notice is hereby given that sealed tenders will be received in this Office up to 2 P.M., on Thursday the 2nd August 1934, for the supply of all or any of the articles specified in annexure for Marthur Farm, and the period of contract to take effect from date of acceptance to end of June 1935.

2. The quantity of each kind mentioned is only approximate and cannot be guaranteed. They must be supplied in such quantities and at such intervals as the Farm Manager, Marthur, may choose to order.

3. Rates quoted must be per unit given in the list for delivery at the Farm, and the amount of each item must be worked out for the quantities indicated and the total amount of all of the items should also be given.

4. No tenders will be accepted unless accompanied by a deposit of Rs. 100 in currency notes as earnest money.

5. The final acceptance of the tender rests with the undersigned who reserves to himself the right of rejecting any tender for all or any of the items therein or for accepting any tender without assigning any reason for so doing.

6. Intimation of acceptance of the tender will be given to the successful tenderer in writing.

7. Within three days after receipt of such acceptance, the successful tenderer will be required to execute the contract bond on the usual Government stamped paper and present the same to the Farm Manager, in default of which his tender will be considered cancelled and his deposit money will be forfeited to Government. The supply of articles should commence within seven days from the date of executing the agreement.

8. The earnest money received from the unsuccessful tenderers will be returned to them in due course by M. O. after deducting the M. O. commission.

The deposit of the successful tenderer will be retained as security deposit for the due fulfilment of the terms of his contract, and it will be returned to him at the termination of the contract, *i.e.*, after the end of June 1935.

9. The decision of the Farm Manager in all questions of acceptance or rejections of any articles supplied is final.

10. The contractor must supply any other article not specified in the list at Market rates, on reasonable notice.

11. No application from the contractor for any sort of concessions whatever in consequence of the rise in the price of the articles in the market due to scarcity, or other causes, will be considered.

12. No advance of cash will be made to the contractor and payment for articles supplied will be made by the Farm Manager, from time to time, as soon as possible after supply, on production of necessary accounts and vouchers in support of bills.

13. In making payment, fractions of "a rupee" in the totals of bills amounting to Rs. 25 or more will be rounded to the nearest rupee, *i.e.*, amounts less than half a rupee will be disregarded and half a rupee or over taken as a rupee. Similarly, in the case of bills for less than Rs. 25, the fractions will be rounded to the nearest anna, *i.e.*, amounts below half-anna being omitted and half anna and over being reckoned as one anna.

14. The contract must not be sublet.